



**Abatement:**

Certified ETSU personnel may conduct the removal of non-friable asbestos if the work involves less than 160 square feet or 260 linear feet or friable TSI if the work involves less than 10 square feet or 25 linear feet. All work will be coordinated to insure minimal exposure to students, faculty, staff and public.

Certified personnel must receive approval from EH&S prior to any abatement activities and must complete an Asbestos Removal Tracking Form (attachment A) for all abatement work. This completed form must be submitted to EH&S monthly. All abatement work will follow the guidelines using appropriate methods. In some cases, removal of asbestos may not be necessary or be the best response action.

Campus renovation projects involving asbestos abatement will utilize certified asbestos abatement contractors. Abatement monitoring shall include air sampling inside and outside containment, and clearance sampling. Clearance air sample results will be communicated to and sent to EH&S before occupancy.

**Disposal:**

Certified asbestos abatement workers will mark the bags appropriately for disposal. Certified asbestos contractors will dispose of asbestos to the landfill as required by EPA and DOT regulations. Once disposed, the contractor is required to send the manifest to EH&S.

